



CAPITAL DISTRICT OFFICE
 547 River Street
 Troy, NY 12180
 P: 518.273.0055 or 888.539.9073
 www.chazencompanies.com

**Village of Chatham
 Water Storage Tank Construction Re-Bid**

**Project No. 31584.01
 DWSRF Project No. 18262**

Addendum No. 1

July 16, 2018

Via Fax

This Addendum forms a part of, and modifies, the original Contract Documents. Each Bidder shall acknowledge receipt of all addenda on the Bid Proposal form included in the Contract Documents. Failure to provide acknowledgement may subject Bidder to disqualification.

The attention of all Bidders is directed to the following modifications to the Contract Documents:

1. Reference Project Manual, Section 001100, Invitation to Bid, bid opening information:
 - a. DELETE the words "July 19, 2018".
 - b. INSERT the words "July 25, 2018" in place of the deleted words.
2. Reference Project Drawings, Sheet G-002 – LAYOUT Note 2:
 - a. INSERT the following sentence at the beginning of this note: "TANK EXCAVATION LAYOUT WILL BE COMPLETED BY OTHERS."
3. Reference Project Drawings, Sheet G-002 – CONSTRUCTION SEQUENCING NOTES Note 14:
 - a. DELETE Note 14.
 - b. INSERT the following in place of the deleted note: "UPON COMPLETION OF THE NEW WATER STORAGE TANK AND PUMP CONTROL SYSTEM, TANK CONTRACTOR SHALL COORDINATE WITH THE VILLAGE AND ELECTRICAL CONTRACTOR FOR COMMISSIONING OF THE SYSTEM. ELECTRICAL CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS TO THE NEW PUMP CONTROL SYSTEM TO ENSURE WATER SYSTEM OPERATES AT EXISTING CONDITIONS BEFORE THE VILLAGE DECOMMISSIONS THE EXISTING OPEN RESERVOIR."

Village of Chatham – Water Storage Tank Construction Re-Bid
Addendum No. 1
July 16, 2018

4. Reference Project Drawings, Sheet C-130 – SITE PLAN, callout indicating 10" MJ GATE VALVE AND CAP FOR FUTURE WATER MAIN CONNECTION:
 - a. INSERT the following at the end of the callout: "(N.I.C.)"
5. Reference Project Drawings, Sheet C-561 – WATER DETAILS, WATER MAIN NOTES:
 - a. INSERT the following at the end of the note heading: "(N.I.C.)"
6. Reference Project Drawings, Sheet C-565 – TANK DETAILS, WATER STORAGE TANK FOUNDATION DESIGN CRITERIA AND CONSTRUCTION PARAMETERS, Note 10:
 - a. DELETE this note.
7. Reference Project Manual, Section 004113, Contract 1 – Tank Construction, Bid Item Descriptions, Part 2 – Work Included:
 - a. REPLACE the sentence: "Temporary sheeting, bracing, and dewatering" with the sentence "Temporary bracing".
 - b. REPLACE the sentence: "Tank mixing system controls and control panel" with the sentence "Furnish and install tank mixing system; furnish tank mixing system control panel (control panel installation and wiring under Contract 2)".
 - c. DELETE the sentence: "Flow maintenance".
8. Reference Project Manual, Section 004113, Contract 2 – Electrical, Bid Item Descriptions, Part 2 – Work Included:
 - a. INSERT the sentence: "Install tank mixing system control panel (control panel provided under Contract 1)".
9. Reference Project Manual, Section 004113, Contract 2 – Electrical, Bid Item Descriptions, Part 3 – Associated Work Not Included:
 - a. INSERT the sentence: "Tank lightning protection (provided under Contract 1)".
10. Reference Project Manual, Section 007310b – Federal Wage Determination:
 - a. DELETE the Federal Wage Determination General Decision Number NY180002 04/27/2018 NY2.
 - b. INSERT the Federal Wage Determination General Decision Number NY180002 07/06/2018 NY2. This document is attached to this addendum.
11. Reference Project Manual, Section 260912 – Control Panels and Integration, Paragraph 1.08 F:

Village of Chatham – Water Storage Tank Construction Re-Bid
Addendum No. 1
July 16, 2018

- a. DELETE the paragraph.
12. Reference Project Manual, Section 260912 – Control Panels and Integration, Paragraph 1.08 G:
 - a. DELETE the sentence: “The Systems Integrator shall be AquaLogics Systems, Inc., 5 Dwight Park Drive, Syracuse, NY 13209, Phone: (315) 413-0400 or approved equal”.
 - b. INSERT the following sentence in place of the deleted sentence: “The Systems Integrator shall be AquaLogics Systems, Inc., 5 Dwight Park Drive, Syracuse, NY 13209, Phone: (315) 413-0400; Kaman Automation Inc., 1000 University Ave, Rochester, NY 14607, Phone: (585) 254-8840; or approved equal”.
 13. Reference Project Manual, Section 331614 – Glass Fused to Steel Bolted Storage Tank, Paragraph 2.02.O.11:
 - a. DELETE the sentence: “The walkway and handrail, if supplied with the roof, shall be constructed of aluminum.”
 - b. INSERT the following sentence in place of the deleted sentence: “Supply a walkway and handrail with the roof. The handrail and walkway shall be constructed of aluminum and extend to the roof vent.”
 14. Reference Project Manual, Section 331614 – Glass Fused to Steel Bolted Storage Tank, Paragraph 2.06.A:
 - a. The Tank Contractor shall refer to Specification Section 264113 and Drawings E-002 and E-006 for additional information regarding the tank lightning protection system.
 - b. The tank lightning protection system shall be furnished and installed under Contract 1 – Tank Construction. Excavation work associated with the lightning protection system shall be performed by others.

END OF ADDENDUM NO. 1